



<b>Project Title:</b>	Brampton Railway Station
<b>Client:</b>	Abellio Greater Anglia
<b>Date of Work:</b>	July 2015

Project description

The platform was subject to extensive sinking of the tarmac platform works caused by trees on adjoining property and was substantially below gauge.

This required the removal of all the existing platform sub base fill material, installation of root barrier and concrete bedding and reinstatement of the platform surfacing, along with re-covering and upgrading electrical works for platform lighting.

Project Constraints

- PTI
- Public Interface
- Plant and material delivery logistics