



Project Title:	Clapham High Street Station
Client:	Network Rail South East
Date of Work:	September 2011

Project description

The existing platform 2 was comprised part traditional build, and part reinforced concrete panels, both of which were in poor condition.

The existing concrete panels were removed, new pcc supporting beams and pcc planks installed. To the traditional section of the platform new copers were installed and platform re-surfaced. New palisade fence installed to rear of platform.

Project Constraints

- PTI
- Public Interface
- Limited track possession
- Access constraints
- Plant and material delivery logistics
- Liaison with local authorities to obtain permits for parking facilities and use of a crane.
- Liaison with residents and businesses in regards to working engineering hours.
- Ecology