



<b>Project Title:</b>	Highbury & Islington Railway Station
<b>Client:</b>	Network Rail
<b>Date of Work:</b>	October 2010

Project description

Traditional re-building works comprising of new copers and re-surfacing of the platform.

New ACO drainage was installed and the existing drainage system was serviced, including checking rainwater goods to the platform canopy.

Brickwork repairs and re-pointing works were undertaken to riser walls at track bed level (under blockade and isolation).

De-vegetation and chemical treatment of the site.

White/ Yellow lining on completion.

All other platforms were subject to re-construction by Carillion.

Project Constraints

PTI

Public Interface

Plant and material delivery logistics

Limited possession period

Ecology