









Project Description

The Cannington disused railway viaduct security fencing at the end of the viaduct was dilapidated and required improving to eliminate unauthorised access.

The original fencing was removed.

A scaffold platform was erected by a nominated scaffolding contractor to provide safe elevated access to the works area.

The structure was accurately measured and Hammond fabricated an improved security fencing arrangement off site.

The newly fabricated fencing arrangement was galvanised, delivered to site and installed.

The new security fencing has now eliminated unauthorised access onto the viaduct.

Project Constraints

Public Interface.

Poor condition of structure.

3rd party negotiations (landowners).

High Level access.

Plant and Materials delivery logistics.

Site Security.